PUBLIC ADVERTISEMENTS.

OFFICE OF CHIEF ELECTRICAL ENGINEER, BANGALORE.

Dated 8th February 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 1st March 1913 for extending the Chief Electrical Engineer's Office, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate and conditions may be seen at the Chief Electrical Engineer's Office at Bangalore, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extend ing the Chief Electrical Engineer's Office, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yds.	140
2	Do filling in basement	"	357
3	Concrete foundation	C. ft.	1,346
4	Stone in mortar, foundation and basement	"	3,095
5	Do superstructure	"	6,976
6	Do circular archwork	"	30
7	Stone slabs roughly dressed	"	320
8	Stone quoins	Sq. ft.	180
9	Pressed brick in mortar pillars	Each	10
10	Brick in mortar	C. ft.	288
11	Pointing with mortar	Sq.	37·27
12	Plastering with mortar...	"	88·92
13	Calcarium washing two coats	"	88·92
14	Dado painting	R. ft.	394
15	Flooring with No. 60 Encaustic flooring tiles	Sq.	24 38
16	Cuddapah slab flooring on 3' concrete and cement painting...	"	9·12
17	First class Mangalore tile roofing with ceiling tiles ...	"	42·25
18	Do roofing	"	11·97
19	Ridge tiles set in mortar	R. ft.	141
20	Zinc guttering and planking	"	96
21	Teakwood turned finials	No.	2
22	Ornamental eave boarding	R. ft.	382
23	W. I. trusses 25 feet clear span put up complete ...	No.	5
24	Do 22 feet do	"	3
25	Teakwood railing	R. ft.	56
26	Do work with wood oiling	C. ft.	325·96
27	Do panelled doors 1½" thick...	Sq. ft.	307
28	Do glazed windows	"	768
29	Do glazed ventilators	"	140
30	Do glazed circular ventilators	"	19
31	Painting	Sq.	23·28

P. F. BEAMES,

Chief Electrical Engineer to the Government of Mysore.